

Koloveč splašková kanalizace II. etapa				
Stoka	PVC DN	DÉLKA STOKY v m	POČET PŘÍPOJEK v ks (PVC DN 150)	DÉLKA PŘÍPOJEK v m
A	300	584,07	27	181,06
A3-1			1	3,95
A3-1-1			1	1,36
A3-1-2	250	13,09	1	1,98
A5			1	106,07
A5-4	300	6,07		
A5-4	600/900	94,52		
AA	250	64,27	7	51,27
A7	250	56,80	2	43,43
A7-1	250	30,10	4	12,62
A8	300	154,41	9	73,30
A8-1	300	21,64	3	8,39
A8-1	250	64,54		
A9			1	5,97
A9-1	300	390,24	23	106,20
A9-1-1	300	27,48	2	10,85
A9-1-2	250	84,35	4	14,53
A9-2	300	107,86	4	32,25
A9-3	250	114,72	12	52,19
A9-3	300	168,76		
A9-3-1	250	63,95	14	121,62
A9-3-1	300	304,23		

A9-3-1-1	300	27,15	3	36,73
A9-3-1-2	300	70,43	3	15,92
A9-3-1-3	250	11,13	1	6,91
A9-3-1-2-1	300	24,05	1	2,13
A9-4	250	63,57	3	12,50
A9-5	250	61,19	4	17,34
A9-6	300	83,11	4	17,26
A10	300	67,62	5	13,64
A10	300	23,67		
A10	400	8,46		
A10	300	21,82		
A10	500	38,10		
A10	600	171,48		
A11	300	199,34	10	44,43
A11-1	300	86,70	7	39,65
A12	300	299,64	29	262,03
A12-1	300	21,39	1	3,09
A13	300	209,22	13	54,67
A14	300	155,67	8	37,70
CELKEM		3994,84	208	1391,04

Přeložka vodovodu ulice Polní			
--------------------------------------	--	--	--

řad PE	d 110	76,00	
--------	-------	-------	--

Přeložka dešťové kanalizace ulice Růžová - stoka A9-1			
--------------------------------------------------------------	--	--	--

stoka PVC	DN 300	56,72	
-----------	--------	-------	--

Přeložka dešťové kanalizace ulice Zahradní - stoka A11			
---------------------------------------------------------------	--	--	--

stoka PVC	DN 300	48,60	
-----------	--------	-------	--